BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2024-25/OW/WORK_INDENT5298

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/09/2024-25, Date: 19-10-2024

Name Of Work: IMPROVEMENTS TO ROADS AND DRAINS AT KUVEMPUNAGARA 1ST STAGE, 2ND STAGE, HOSABALUNAGARA, ASHRAYA LAYOUT , SINGAPURA, NAIDU LAYOUT, MAARIYAMMA BLOCK AND SURROUNDING AREAS IN WARD NO. 11 NEW WARD NO 14 (KUVEMPUNAGARA).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sri. P Vishwanath	
				In Figures	In Words
1	616.68	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. In all kinds of soils Depth upto 1.5 m	Cum	300.00	Rupees Three Hundred Only
2	111.59	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. . Mix 1:4:8 Using 40 mm nominal size graded crushed coarse aggregates	Cum	6500.00	Rupees Six Thousand Five Hundred Only
3	15.16	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification H. All other type of structures	Tonne	90000.00	Rupees Ninety Thousand Only
4	244.24	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	7850.00	Rupees Seven Thousand Eight Hundred Fifty Only

Signature of the Contractor

Executive Engineer

Name Of Work: IMPROVEMENTS TO ROADS AND DRAINS AT KUVEMPUNAGARA 1ST STAGE, 2ND STAGE, HOSABALUNAGARA, ASHRAYA LAYOUT , SINGAPURA, NAIDU LAYOUT, MAARIYAMMA BLOCK AND SURROUNDING AREAS IN WARD NO. 11 NEW WARD NO 14 (KUVEMPUNAGARA).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sri. P Vishwanath	
				In Figures	In Words
5	8.93	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:2:4 Using 20 mm nominal size graded crushed coarse aggregate	Cum	6900.00	Rupees Six Thousand Nine Hundred Only
6	582.75	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drain age of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete.	Sqm	1300.00	Rupees One Thousand Three Hundred Only
7	44.64	Providing and Fixing pre cast Covering Slab 230mm thick made out of M20 and jelly 20mm Down size with steel reinforcement including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge	Sqm	5104.00	Rupees Five Thousand One Hundred Four Only
8	616.68	Unloading, Loading & Carriage of Materials Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum. (Tipper 5.5 m3)	Cum	150.00	Rupees One Hundred Fifty Only
9	789.35	Cost of Haulage Excluding Loading and Unloading,Taking output 10 t load and lead 10 km = 100 t.km	T.Km	200.00	Rupees Two Hundred Only

P. Vishwanath

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike